



Issued March 8, 2010

**NOTICE TO ALL PROSPECTIVE BIDDERS**

**RE: ADDENDUM 2**

**2010-RPC-005 Prince Edward Community Centre Hall Renovations**

This Addendum is being issued to change and/or provide clarification and additional requirements for the specifications of the unit to be bid. The changes are summarized below.

A2 1.

The Community Hall is the single largest meeting space in the County and as such is required by the County for various large meetings throughout the year. The contractor will be able to work on the renovation from Sunday to Thursday starting May 29<sup>th</sup> and but must have completed the renovations by July 1<sup>st</sup>, 2010, in order to ensure the project is not dragged out.

The contractor must have the hall cleaned and have disposed of any debris by Friday of each week of construction as the hall and kitchen are rented out on the weekends.

A2.2

**A completed schedule of construction must be included with your tender submission, including facility availabilities (i.e. availability of Hall on what days/availability of kitchen on what days).**

A2.3

Room Finish Schedule

Location: Ceilings

- Delete Armstrong co-extended aluminum clean room 15/16" exposed tee system. (all ceilings )
- Add standard 15/16" tee-bar system.

A 2.4

Main Floor Plan

Note on drawing – OBC 2006: 3.8.1.5 (1) Controls

- Intent: Relocated control boxes and junction boxes where required, to be installed backing plate which will then be mounted on concrete block surface using durable appearance grade fasteners. Backing plate to extend 2" minimum around control box being supported. Where control box and junction box are mounted through the same backing plate they shall be 2" minimum apart. Backing plate material to be 1" thick plastic toilet partition material. Colour to compliment wall colour.

---

Received by (Company Name)

---

Date, Time